

PCT REQUEST

WGEC/0013PC

Original (for SUBMISSION) - printed on 28.10.2003 10:50:06 AM

0	For receiving Office use only	PCT/US 03 /34209 (28.10.03) 28 OCT 2003
0-1	International Application No.	
0-2	International Filing Date	
0-3	Name of receiving Office and "PCT International Application"	PCT INTERNATIONAL APPLICATION RO/US
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.92 (updated 01.04.2003)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	United States Patent and Trademark Office (USPTO) (RO/US)
0-7	Applicant's or agent's file reference	WGEC/0013PC
I	Title of invention	A METHOD FOR ESTIMATING POROSITY AND SATURATION IN A SUBSURFACE RESERVOIR
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	WESTERN GECO, LLC
II-5	Address:	10001 Richmond Avenue Houston, TX 77042 United States of America
II-6	State of nationality	US
II-7	State of residence	US
II-8	Telephone No.	(713) 689-2626
II-9	Facsimile No.	(713) 689-1977
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	BACHRACH, Ran
III-1-5	Address:	United States of America
III-1-6	State of nationality	
III-1-7	State of residence	US

PCT REQUEST

WGEC/0013PC

Original (for SUBMISSION) - printed on 28.10.2003 10:50:06 AM

III-2	Applicant and/or inventor	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	DUTTA, Nader
III-2-5	Address:	
III-2-6	State of nationality	
III-2-7	State of residence	
	(The country of the address indicated for this person is the applicant's State (i.e. country) of residence if no State of residence is indicated here)	
IV-1	Agent or common representative; or address for correspondence	
	The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name (LAST, First)	PATTERSON, William, B.
IV-1-2	Address:	Moser, Patterson & Sheridan, LLP 3040 Post Oak Blvd. Suite 1500 Houston, TX 77056 United States of America
IV-1-3	Telephone No.	(713) 623-4844
IV-1-4	Facsimile No.	(713) 623-4846
IV-1-5	e-mail	bpatterson@mpsllp.com
IV-1-5	Agent's registration No.	34,102
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE BG CH&LI CY CZ DE DK EE ES FI FR GB GR HU IE IT LU MC NL PT RO SE SI SK TR and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT

PCT REQUEST

WGEC/0013PC

Original (for SUBMISSION) - printed on 28.10.2003 10:50:06 AM

V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT AU AZ BA BB BG BR BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NI NO NZ OM PG PH PL PT RO RU SC SD SE SG SK SL SY TJ TM TN TR TT TZ UA UG US UZ VC VN YU ZA ZM ZW		
V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.			
V-6	Exclusion(s) from precautionary designations	NONE		
VI	Priority claim	NONE		
VII-1	International Searching Authority Chosen	European Patent Office (EPO) (ISA/EP)		
VIII	Declarations	Number of declarations		
VIII-1	Declaration as to the identity of the inventor	-		
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	-		
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-		
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-		
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-		
IX	Check list	number of sheets		electronic file(s) attached
IX-1	Request (including declaration sheets)	4	-	
IX-2	Description	8	-	
IX-3	Claims	4	-	
IX-4	Abstract	1		EZABST00.TXT
IX-5	Drawings	2	-	
IX-7	TOTAL	19		

PCT REQUEST

WGEC/0013PC

Original (for SUBMISSION) - printed on 28.10.2003 10:50:06 AM

	Accompanying items	paper document(s) attached	electronic file(s) attached
IX-8	Fee calculation sheet	✓	-
IX-11	Copy of general power of attorney	✓	-
IX-17	PCT-EASY diskette	-	Diskette
IX-19	Figure of the drawings which should accompany the abstract	1	
IX-20	Language of filing of the international application	English	
X-1	Signature of applicant, agent or common representative	<i>William B. Patterson</i>	
X-1-1	Name (LAST, First)	PATTERSON, William, B.	

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	(28.10.03) TO2 Rec'd PCT/PTO 28 OCT 2003
10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/EP
10-6	Transmittal of search copy delayed until search fee is paid	

FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

PCT (ANNEX - FEE CALCULATION SHEET)

WGEC/0013PC


Original (for SUBMISSION) - printed on 28.10.2003 10:50:06 AM

(This sheet is not part of and does not count as a sheet of the international application)

0	For receiving Office use only	PCT/US 03 /34209		
0-1	International Application No.			
0-2	Date stamp of the receiving Office	(28.10.03) 28 OCT 2003		
0-4	Form - PCT/RO/101 (Annex) PCT Fee Calculation Sheet	PCT-EASY Version 2.92 (updated 01.04.2003)		
0-4-1	Prepared using			
0-9	Applicant's or agent's file reference	WGEC/0013PC		
2	Applicant	WESTERN GECCO, LLC, et al.		
12	Calculation of prescribed fees	fee amount/multiplier	Total amounts (USD)	
12-1	Transmittal fee T	⇒	240	240
12-2-1	Search fee S	⇒	1,020	4,119
12-2-2	International search to be carried out by	EP		
12-3	International fee			
	Basic fee			
	(first 30 sheets) b1	476		
12-4	Remaining sheets	0		
12-5	Additional amount (X)	12		
12-6	Total additional amount b2	0		
12-7	b1 + b2 = B	476		
12-8	Designation fees			
	Number of designations contained in international application	97		
12-9	Number of designation fees payable (maximum 5)	5		
12-10	Amount of designation fee (X)	104		
12-11	Total designation fees D	520		
12-12	PCT-EASY fee reduction R	-148		
12-13	Total International fee (B+D-R) I	⇒	848	848
12-17	TOTAL FEES PAYABLE (T+S+I+P)	⇒	2,108	2,201
12-19	Mode of payment	authorization to charge deposit account		
12-20	Deposit account instructions			
	The receiving Office:	United States Patent and Trademark Office (USPTO) (RO/US)		
12-20-1	Authorization to charge the total fees indicated above.	✓		
12-20-2	Authorization to charge any deficiency or credit any overpayment in the total fees indicated above.	✓		
12-20-3	Authorization to charge the fee for priority document.	✓		
12-21	Deposit account No.	20-0782		
12-22	Date	28 October 2003 (28.10.2003)		

PCT (ANNEX - FEE CALCULATION SHEET)

Original (for SUBMISSION) - printed on 28.10.2003 10:50:06 AM

12-23	Name and signature	PATTERSON, William, B. 
-------	--------------------	--

VALIDATION LOG AND REMARKS

13-2-3	Validation messages Names	Yellow Applicant 2.:Street address missing
		Yellow Applicant 2.:City missing
		Yellow Applicant 2.: US State missing
		Yellow Applicant 2.:Postal code missing
		Yellow Applicant 2.:State of Nationality missing
		Yellow Applicant 3.: "Country or territory" indication missing
		Yellow Applicant 3.:Street address missing
		Yellow Applicant 3.:City missing
		Yellow Applicant 3.:Postal code missing
		Yellow Applicant 3.:State of Nationality missing
		Yellow Applicant 3.:State of Residence missing
13-2-4	Validation messages Priority	Green? No priority of an earlier application has been claimed. Please verify
13-2-7	Validation messages Contents	Green? Reference number for attached copy of general power of attorney not indicated.
13-2-9	Validation messages Payment	Green? Please ensure that you have a valid deposit account with the receiving Office selected.

POWER OF ATTORNEY

(for an international application filed under the Patent Cooperation Treaty)

(PCT Rule 90.4)

The undersigned applicant(s) *(Names should be indicated as they appear in the request):*

WesternGeco, L.L.C.
10001 Richmond Avenue
Houston, TX 77042
US

hereby appoints (appoint) the following person as:



agent



common representative

Name and address*(Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)*

PATTERSON, William, B. (Reg. No. 34,102); PATTERSON, B. Todd (Reg. No. 37,906); TACKETT, Keith M. (Reg. No. 32,008); SHERIDAN, James A. (Reg. No. 24,435); MOSER, JR., Raymond M. (Reg. No. 34,682); MCCLELLAN, Gero G. (Reg. No. 44,227); all with the firm of MOSER, PATTERSON & SHERIDAN, L.L.P., 3040 Post Oak Blvd., Suite 1500, Houston, TX 77056, US;

to represent the undersigned before



all the competent International Authorities



the International Searching Authority only



the International Preliminary Examining Authority only

in connection with the international application identified below:

Title of the invention: A METHOD FOR ESTIMATING POROSITY AND SATURATION IN A
SUBSURFACE RESERVOIR

Applicant's or agent's file reference: WGEC/0013 PC

International application number (if already available):

filed with the following Office United States of America as receiving Office
and to make or receive payments on behalf of the undersigned.

Signature of the applicant(s) *(where there are several applicants, each of them must sign; next to each signature, indicate the name of the person signing and the capacity in which the person signs, if such capacity is not obvious from reading the request or this power):*

WESTERNGECO, L.L.C.

By: _____
LUIS CANALES, VICE PRESIDENT

Date: _____

A METHOD FOR ESTIMATING POROSITY AND SATURATION IN A SUBSURFACE RESERVOIR

BACKGROUND OF THE INVENTION

Field of the Invention

[0001] Embodiments of the present invention generally relate to a method for estimating subsurface reservoir properties, such as porosity and saturation.

Description of the Related Art

[0002] For many years seismic exploration for oil and gas has been conducted by use of a source of seismic energy and the reception of the energy generated by the source by an array of seismic detectors. On land, the source of seismic energy may be a high explosive charge or another energy source having the capacity to deliver a series of impacts or mechanical vibrations to the earth's surface. Acoustic waves generated by these sources travel downwardly into the earth's subsurface and are reflected back from strata boundaries and reach the surface of the earth at varying intervals of time, depending on the distance traveled and the characteristics of the subsurface traversed. These returning waves are detected by the sensors, which function to transduce such acoustic waves into representative electrical signals. The detected signals are recorded for later processing using digital computers. Typically, an array of sensors is laid out along a line to form a series of detection locations. More recently, seismic surveys are conducted with sensors and sources laid out in generally rectangular grids covering an area of interest, rather than along a single line, to enable construction of three dimensional views of reflector positions over wide areas. Normally, signals from sensors located at varying distances from the source are added together during processing to produce "stacked" seismic traces. In marine seismic surveys, the source of seismic energy is typically air guns. Marine seismic surveys typically employ a plurality of sources and/or a plurality of streamer cables, in which seismic sensors are mounted, to gather three dimensional data.

[0003] Initially, seismic traces were used simply for ascertaining formation structure. Recently, however, exploration geophysicists have subsequently developed a plurality of time-series transformations of seismic traces to obtain a

variety of characteristics that describe the traces, which are generally referred to as "attributes". Attributes may be computed prestack or poststack. Poststack attributes include reflection intensity, instantaneous frequency, reflection heterogeneity, acoustic impedance, velocity, dip, depth and azimuth. Prestack attributes include moveout parameters such as amplitude-versus-offset (AVO), and interval and average velocities.

[0004] It has been observed that specific seismic attributes are related to specific subsurface properties. For example, reservoir porosity and the hydrocarbon saturation may be estimated from surface seismic data to predict the amount of oil or gas reserves in the subsurface reservoirs. Generally, the reservoir porosity is estimated while keeping the hydrocarbon saturation fixed, and the hydrocarbon saturation is estimated while keeping the reservoir porosity fixed. Such methodology, however, often leads to inaccurate estimates of the porosity and saturation.

[0005] Therefore, a need exists in the art for an improved method for estimating porosity and saturation in a subsurface reservoir.

SUMMARY OF THE INVENTION

[0006] Embodiments of the present invention are generally directed to a method for estimating a porosity and a saturation in a subsurface formation. The method includes determining a plurality of relationships relating a plurality of parameters that govern wave propagation in the subsurface formation to the porosity and the saturation in the subsurface formation, forward modeling a plurality of seismic attributes using the relationships to derive a plurality of conditional probability density functions for the seismic attributes, applying a Bayesian inversion to the conditional probability density functions for the seismic attributes to derive a joint probability density function for the porosity and the saturation in the subsurface formation, and integrating the joint probability density function for the porosity and the saturation to derive a probability density function for the porosity and a probability density function for the saturation.

[0007] In one embodiment, the method further includes mapping the probability density function for the porosity to a plurality of observed seismic attributes to generate an estimate for the porosity.

[0008] In another embodiment, the method further includes mapping the probability density function for the saturation to a plurality of observed seismic attributes to generate an estimate for the saturation.

[0009] In yet another embodiment, the parameters are a bulk modulus (K), a shear modulus (G) and a bulk density (ρ).

BRIEF DESCRIPTION OF THE DRAWINGS

[0010] The following detailed description makes reference to the accompanying drawings, which are now briefly described.

[0011] Figure 1 illustrates a flow diagram of a method for estimating reservoir porosity and hydrocarbon saturation in a subsurface reservoir in accordance with one embodiment of the invention.

[0012] Figure 2 illustrates a computer network into which embodiments of the invention may be implemented.

[0013] While the invention is described herein by way of example for several embodiments and illustrative drawings, those skilled in the art will recognize that the invention is not limited to the embodiments or drawings described. It should be understood, that the drawings and detailed description thereto are not intended to limit the invention to the particular form disclosed, but on the contrary, the intention is to cover all modifications, equivalents and alternatives falling within the spirit and scope of the present invention as defined by the appended claims. The headings used herein are for organizational purposes only and are not meant to be used to limit the scope of the description or the claims.

DETAILED DESCRIPTION

[0014] Figure 1 illustrates a flow diagram of a method 100 for estimating reservoir porosity and hydrocarbon saturation in a subsurface reservoir in accordance with one embodiment of the invention. At step 10, mathematical relationships relating the fundamental physical parameters that govern the elastic wave propagation in the subsurface reservoir to the porosity and the saturation in the subsurface reservoir are determined. For a linear isotropic subsurface reservoir, the fundamental physical parameters are the bulk modulus (K), the shear modulus (G) and the bulk density (ρ). As such, the bulk modulus (K) is a function of the porosity and the saturation, the shear modulus G is a function of the porosity, and the bulk density (ρ) is a function of the porosity and the saturation. In one embodiment, the mathematical relationships are determined using rock physics relations, including Biot-Gassmann relations. Other types of media may require mathematical relationships relating other fundamental physical parameters to the porosity and the saturation.

[0015] At step 20, one or more seismic attributes (e.g., seismic velocity, acoustic impedance, shear impedance, far offset impedance, etc) are forward modeled using the mathematical relationships, e.g., the bulk modulus (K), the shear modulus (G) and the bulk density (ρ). Generally, seismic attributes are fields that are related to the fundamental physical parameters governing the seismic wave propagation in the subsurface reservoir, e.g., the bulk modulus (K), the shear modulus G, and the bulk density (ρ). For example, compression wave velocity (V_p) and shear wave velocity (V_s) are related to the fundamental physical parameters by the following equations:

$$V_p = \sqrt{[(K + 4G/3)/\rho]} \quad (\text{Equation 1}).$$

$$V_s = \sqrt{(G/\rho)} \quad (\text{Equation 2}).$$

Acoustic impedance is related to the fundamental physical parameters by the following equation:

$$AI = V_p * \rho \quad (\text{Equation 3}).$$

Shear impedance is related to the fundamental physical parameters by the following equation:

$$SI = V_s * \rho \quad (\text{Equation 4}).$$

As such, the seismic attributes may be simulated using the mathematical relationships relating the fundamental physical parameters that govern the elastic wave propagation in the subsurface reservoir to the porosity and the saturation in the subsurface reservoir.

[0016] In one embodiment, the seismic attributes are forward modeled using stochastic rock physics, such as Monte Carlo simulation. As such, a plurality of porosity and saturation values is randomly drawn, a seismic attribute is simulated, and a conditional probability density function for the seismic attribute is derived. The process is then repeated for all the seismic attributes. In this manner, the conditional probability density functions for all the seismic attributes are synthetically derived without using actual seismic data. The conditional probability density function may also be referred to as the likelihood function.

[0017] At step 30, the joint probability density function of the porosity and the saturation is derived. In one embodiment, a Bayesian inversion is applied to the conditional probability density functions for the seismic attributes to derive the joint probability density function for the porosity and the saturation. In the previous step, the conditional probability density functions for the seismic attributes were derived, given the porosity and saturation values. Using the Bayesian inversion, the joint probability density function for the porosity and the saturation may be derived, given the seismic attributes. The joint probability density function for the porosity and the saturation may be expressed as:

$$p(\phi, sw|ATR) = p(\phi, sw) \times p(ATR|\phi, sw) / p(ATR) \quad (\text{Equation 5}),$$

where $p(\phi, sw)$ represents the prior expected porosity and saturation distribution in the reservoir, $p(ATR|\phi, sw)$ represents the conditional probability density functions of the seismic attributes given the porosity and the saturation values, and $p(ATR)$ represents the prior distribution of the seismic attributes.

[0018] At step 40, the marginal probability density functions for the porosity and the saturation are derived. In one embodiment, the marginal probability density functions for the porosity and the saturation are derived by integrating the joint probability density function for the porosity and the saturation. In this manner, a separate probability density function for the porosity is derived and a separate probability density function for the saturation is derived. The probability density function for the porosity may be expressed as:

$$p(\phi | ATR) = \int p(\phi, sw | ATR) dsw \quad (\text{Equation 6}).$$

The probability density function for the saturation may be expressed as:

$$p(sw | ATR) = \int p(\phi, sw | ATR) d\phi \quad (\text{Equation 7}).$$

[0019] At step 50, the probability density function for the porosity is mapped to a set of observed seismic attributes to generate an estimate for the porosity in the subsurface reservoir for the set of observed seismic attributes. A set of observed seismic attributes may include one or more observed seismic attributes. For example, a set of observed seismic attributes may include three observed seismic attributes – compression wave velocity, shear wave velocity and density. In one embodiment, the probability density function of porosity is mapped to the set of observed seismic attributes using a maximum a posteriori (MAP) estimator. As such, the most likely porosity value is selected from the probability density function for porosity for the set of observed seismic attributes. In a further embodiment, the standard deviation or quintiles of distribution for the estimated porosity value may be generated. Typically, the quintile value of a distribution is the value that a proportion of the data does not exceed. A quintile value generally ranges from 0 to 1.

[0020] At step 60, the probability density function for saturation is mapped to a set of observed seismic attributes to generate an estimate for the saturation in the subsurface reservoir for the set of observed seismic attributes. As mentioned above, a set of observed seismic attributes may include any number of observed seismic attributes. In one embodiment, the probability density function of saturation is mapped to the observed seismic attributes using a maximum a posteriori (MAP) estimator. As such, the most likely saturation value is selected from the probability

density function for saturation for the set of observed seismic attributes. In a further embodiment, the standard deviation or quintiles of distribution for the estimated saturation value may be generated.

[0021] Figure 2 illustrates a computer network 200, into which embodiments of the invention may be implemented. The computer network 200 includes a system computer 230, which may be implemented as any conventional personal computer or workstation, such as a UNIX-based workstation. The system computer 230 is in communication with disk storage devices 229, 231, and 233, which may be external hard disk storage devices. It is contemplated that disk storage devices 229, 231, and 233 are conventional hard disk drives, and as such, will be implemented by way of a local area network or by remote access. Of course, while disk storage devices 229, 231, and 233 are illustrated as separate devices, a single disk storage device may be used to store any and all of the program instructions, measurement data, and results as desired.

[0022] In one embodiment, seismic data from geophones are stored in disk storage device 231. The system computer 230 may retrieve the appropriate data from the disk storage device 231 to perform the porosity and saturation estimation according to program instructions that correspond to the methods described herein. The program instructions may be written in a computer programming language, such as C++, Java and the like. The program instructions may be stored in a computer-readable memory, such as program disk storage device 233. Of course, the memory medium storing the program instructions may be of any conventional type used for the storage of computer programs, including hard disk drives, floppy disks, CD-ROMs and other optical media, magnetic tape, and the like.

[0023] According to the preferred embodiment of the invention, the system computer 230 presents output primarily onto graphics display 227, or alternatively via printer 228. The system computer 230 may store the results of the methods described above on disk storage 229, for later use and further analysis. The keyboard 226 and the pointing device (e.g., a mouse, trackball, or the like) 225 may be provided with the system computer 230 to enable interactive operation.

[0024] The system computer 230 may be located at a data center remote from the survey region. The system computer 230 is in communication with geophones (either directly or via a recording unit, not shown), to receive signals indicative of the reflected seismic energy. These signals, after conventional formatting and other initial processing, are stored by the system computer 230 as digital data in the disk storage 231 for subsequent retrieval and processing in the manner described above. While Figure 2 illustrates the disk storage 231 as directly connected to the system computer 230, it is also contemplated that the disk storage device 231 may be accessible through a local area network or by remote access. Furthermore, while disk storage devices 229, 231 are illustrated as separate devices for storing input seismic data and analysis results, the disk storage devices 229, 231 may be implemented within a single disk drive (either together with or separately from program disk storage device 233), or in any other conventional manner as will be fully understood by one of skill in the art having reference to this specification.

[0025] While the foregoing is directed to embodiments of the present invention, other and further embodiments of the invention may be devised without departing from the basic scope thereof, and the scope thereof is determined by the claims that follow.

What Is Claimed Is:

1. A method for estimating a porosity and a saturation in a subsurface formation, comprising:

determining a plurality of relationships relating a plurality of parameters that govern wave propagation in the subsurface formation to the porosity and the saturation in the subsurface formation;

forward modeling a plurality of seismic attributes using the relationships to derive a plurality of conditional probability density functions for the seismic attributes;

applying a Bayesian inversion to the conditional probability density functions for the seismic attributes to derive a joint probability density function for the porosity and the saturation in the subsurface formation; and

integrating the joint probability density function for the porosity and the saturation to derive a probability density function for the porosity and a probability density function for the saturation.

2. The method of claim 1, further comprising mapping the probability density function for the porosity to a set of observed seismic attributes to generate an estimate for the porosity for the set of observed seismic attributes.

3. The method of claim 2, wherein the probability density function for the porosity is mapped to the observed seismic attributes using a maximum a posteriori estimator.

4. The method of claim 2, further comprising generating one of a standard deviation and one or more quintiles for the estimate for the porosity.

5. The method of claim 1, further comprising mapping the probability density function for the saturation to a set of observed seismic attributes to generate an estimate for the saturation for the set of observed seismic attributes.

6. The method of claim 5, wherein the probability density function for the saturation is mapped to the observed seismic attributes using a maximum a posteriori estimator.

7. The method of claim 5, further comprising generating one of a standard deviation and one or more quintiles for the estimate for the saturation.
8. The method of claim 1, wherein the step of forward modeling comprises:
randomly drawing a plurality of porosity and saturation values;
simulating the seismic attributes from the porosity and saturation values; and
deriving the conditional probability density functions for the seismic attributes.
9. The method of claim 1, wherein the parameters comprise a bulk modulus (K), a shear modulus (G) and a bulk density (ρ).
10. The method of claim 1, wherein the relationships are determined using rock physics.
11. The method of claim 1, wherein the seismic attributes are forward modeled using stochastic rock physics.
12. The method of claim 1, wherein the subsurface formation is a subsurface reservoir.
13. The method of claim 1, wherein the relationships are mathematical relationships.
14. The method of claim 1, wherein the parameters govern one of elastic and inelastic wave propagation in the subsurface formation.
15. A computer readable medium containing a program which, when executed, performs an operation, comprising:
determining a plurality of relationships relating a plurality of parameters that govern wave propagation in the subsurface formation to the porosity and the saturation in the subsurface formation;
forward modeling a plurality of seismic attributes using the relationships to derive a plurality of conditional probability density functions for the seismic attributes;
applying a Bayesian inversion to the conditional probability density functions for the seismic attributes to derive a joint probability density function for the porosity and the saturation in the subsurface formation; and

integrating the joint probability density function for the porosity and the saturation to derive a probability density function for the porosity and a probability density function for the saturation.

16. The computer readable medium of claim 15, wherein the operation further comprises mapping the probability density function for the porosity to a plurality of observed seismic attributes to generate an estimate for the porosity.

17. The computer readable medium of claim 15, wherein the operation further comprises mapping the probability density function for the saturation to a plurality of observed seismic attributes to generate an estimate for the saturation.

18. The computer readable medium of claim 15, wherein the step of forward modeling comprises:

- randomly drawing a plurality of porosity and saturation values;
- simulating the seismic attributes from the porosity and saturation values; and
- deriving the conditional probability density functions for the seismic attributes.

19. The computer readable medium of claim 15, wherein the parameters comprise a bulk modulus (K), a shear modulus (G) and a bulk density (ρ).

20. A method for estimating a porosity and a saturation in a subsurface formation, comprising:

- determining a plurality of relationships relating a plurality of parameters that govern wave propagation in the subsurface formation to the porosity and the saturation in the subsurface formation;

- forward modeling a plurality of seismic attributes using the relationships to derive a plurality of conditional probability density functions for the seismic attributes;

- applying a Bayesian inversion to the conditional probability density functions for the seismic attributes to derive a joint probability density function for the porosity and the saturation in the subsurface formation;

- integrating the joint probability density function for the porosity and the saturation to derive a probability density function for the porosity and a probability density function for the saturation;


mapping the probability density function for the porosity to a set of observed seismic attributes to generate an estimate for the porosity for the set of observed seismic attributes; and

mapping the probability density function for the saturation to a set of observed seismic attributes to generate an estimate for the saturation for the set of observed seismic attributes.

21. The method of claim 20, wherein the parameters comprise a bulk modulus (K), a shear modulus (G) and a bulk density (ρ).

ABSTRACT

A method and apparatus for estimating a porosity and a saturation in a subsurface formation. The method includes determining a plurality of relationships relating a plurality of parameters that govern wave propagation in the subsurface formation to the porosity and the saturation in the subsurface formation, forward modeling a plurality of seismic attributes using the relationships to derive a plurality of conditional probability density functions for the seismic attributes, applying a Bayesian inversion to the conditional probability density functions for the seismic attributes to derive a joint probability density function for the porosity and the saturation in the subsurface formation, and integrating the joint probability density function for the porosity and the saturation to derive a probability density function for the porosity and a probability density function for the saturation.



2/2




FIG. 2